

Amplified

15-135-21459
21-16-23W

D R I L L E R S L O G

#1 Dietterich

CASING RECORD: 8 jts. used 8-5.8" surface casing	COMPANY: Beren Corporation	DESCRIPTION: SE NW Section 21-16S-23W Ness County, Kansas
TOTAL ROTARY DEPTH: 4463'	CONTRACTOR: Strata Drilling Company	
	COMMENCED: June 13, 1978	
	COMPLETED: June 20, 1978	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand	0	338	Ran 324' used 8-5/8" surface casing,
Sand, shale	338	1820	set and cemented @ 329' with 200
Anhydrite	1820	1855	sacks 60-40 pozmix, 2% gel, 3% C.C.
Shale and shells	1855	2527	Cement circulated. Plug down at
Lime and shale	2527	4445	8:45 p.m., June 13, 1978.
Lime	4445	4463	
			Ran two drill stem tests.
			Ran one electric log.
			Ran 122 jts. new 4 1/2" casing, set and
			cemented @ 4455' with 250 sacks
			60-40 pozmix, 10% salt. Plug down
			at 1:25 a.m., June 20, 1978.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1978

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the
best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp