


State Kansas County Stafford
 Company G-M-R Oil Co. Well No. 1
 Farm Pundsack "A"
 Survey 1929 D.F.
 Block No. 21 Sec. 19 Twp. 21 Range 13W
 Co-Ord. Elev. 1932 R.B.

NW NW SW



Standard 2.0.

Pundsack Pool

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line Ft. from S. Line

Ft. from W. Line Ft. from E. Line

Date	Depth	
12-24-50		MIRT, RUR
12-28		Spud - 8 5/8" @ -160'
12-30	555	Drlg.
	818	Anhydrite, plus 1113
12-31	1600	Drlg.
1-1-51	2320	Drlg.
1-2-51	2680	Drlg.
1-5-51	3210	Drlg.
1-6-51	3367	Brown Lansing

Date	Depth	715078
	3378	Lansing (-1447)
	3411-14	Sli. foss. ls. w/fair vug. por. sli. sptd. sat. - no odor
	3449-53	ls, xln, cherty, poor por. tr. stn.
	3411-55	D.S.T. 3511-55, open 1 hrs. rec.-300' GSW - 940# BHP
	3471-77	ool. ooc. good por. no stn. or odor, prob. water
	3505-09	ool. ooc, good por. tr. dk. oil stn, prob. water.
	3519-22	ooc. fair por. 10% sptd. sat.
	3536-42	sli. foss ls, poor-fair por. poor sptd. sat. - asphaltic residue
	3544-46	Ditto
	3557-65	ls, xln, chalky, partly foss. tr. good vug. por. poor sptd. sat. - no odor
	3519-66	D.S.T. open 45 min. 15# BHP - 620# BHP. rec. 120' HOCM (50% ool) plus 30' free oil
	3587-93	Partly foss poor vug. por. poor sptd. sat.

State Kansas County Stafford

Company G-M-R Oil Co. Well No. 1


Farm Pundsack "A"

Survey

Block No. Sec. 19 Twp. 21 Range 13W

Co-Ord. Elev. 1932 R.B.

NW NW SW



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
	3627	Conglomerate (-1695)
	3635	Cherty Viola (-1703)
	3668	Simpson (-1736)
	3710	Drlg.
	3720	Arbuckle (-1788)
	3722	R.T.D. Med. crys. dolo. fr. poro. & sat.
		5½" @ 3721 - dp, co, dr ½"
		Shut down 12 hrs.

715078

Date	Depth	
		Fill 2 GO & 2 BW
		250 acid - fill 1450' water
	-1808	of which was 5 Gal. oil
3740		T.D. dd, water p.b. 5 GO
		and 10BW (-1388)
		Perf. 36 - 3560-69
	"	32 - 3540-48
		2000 gal. acid
		SW _b . 7 BO for 1 hr.
		Swb. 3 BO for 1 hr.
		Swb. 2 BO for 1 hrs.
		Perf. 7 - 3512-24
		4000 acid
1-19		Swb. 25 BWPH
		Sq. 100 sx. dc.
		Acid 4000 gal.
		Swb. 1 BOPH plus 20 BWPH
		for 3 hrs.
		D & A