


Date	Depth	
		715082
	3421-25	F. crys., cherty, poor vug. poro. lt. sptd. sat. odor
	3456-62	Poor vug. poro. lt. sptd. stain
	3473-82	Partly oolic, fr. poro. lit stain
	3508-19	Foss. Poor poro. shaley
	3522-24	Ditto
	3547-53	cherty, poor vug. poro. lt. sptd. sat.
	3568-74	f. crys., shly. vug. poro. sptd. sat.
1-29-51	3574-78	poor vug. por. fr. sptd. sat.
D.S.T.	3567-84	Open 45 min. ^{cl 15" wk cl 10"} rec. 15' mud No BHP
	3641	Conglomerate (-1718)
	3656	Viola /-1733)
	3694	Simpson (-1771)
	3744	Arbuckle ⁽⁻¹⁸²¹⁾ dolo. m. crys. sptd. sat.
	3748	T.D.
D.S.T.	3745-48	Open 30" ^{cl 15"} , weak blow ^{for 3"} , rec. 30. ft. mud - no BHP
	3746	5 1/2" casing 75 ft.

State Kansas County Stafford
 Company G-M-R Well No. 2
 Farm H. Baier
 Survey _____
 Block No. _____ Sec. 25 Twp. 21S Range 14W
 Co-Ord. _____ Elev. _____

SE SE NE



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
R.T.D.	3748	dp. Red loc dry. 1 G.O. 8 G.W.
2-4-51	MICT	
2-5-51		Fill 50' OCM. C. O.
		750# 5 hrs.
		500 Acid - 1250#
2-6		Est. 5 BOPH, Tstg. for 3 hrs. pumped 51 BO
2-13	Pump	
2-15	Pump	53 BO in 8 hrs. NW

[illegible]