

State Kansas County Trego

Company GMR Well No. 1

Farm Moore

Survey

Block No. Sec. 35 Twp. 14S Range 21W

Co-Ord. Elev. 2084 KB

SE SE NE


- 1/4-GMR
- 1/8-Reinach
- 1/8-Carnegie
- 1/2-Carter, et al

DHM-Stanolind \$2500  
 GMR Tools

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line \_\_\_\_\_ Ft. from S. Line \_\_\_\_\_  
 Ft. from W. Line \_\_\_\_\_ Ft. from E. Line \_\_\_\_\_

Date	Depth	
		MIRT & SPD 4-14-52
4-15		8 5/8" @ 216' w/120 sx
4-17	1650	Drlg
	1900	Drlg
	2370	Drlg
4-21	3300	Drlg
4-22	3374	Heebner (-1290)
	3396	Toronto (-1312)
	3416	Lansing (-1332)
4-23	DST 3483-3505,	op 1 hr, cl 15". Wk bl

Date	Depth	715094 PT
		for 35". Rec 60' mdy SW.
		BHP-1200#
	3505	Drlg
4-24	3740	Drlg
		DST 3752-92, op 45", <sup>cl 15"</sup> Sli bl 3". Rec 30'
		mud, BHP-850
	3817	Cherty Congl (-1733)
	3843	Drlg
4-28	Log Tops:	
	3377	Heebner (-1293)
	3398	Toronto (-1314)
	3416	Lansing (-1332)
	3666	B/KC (-1582)
	3750	Miss (-1666)
	3786	Kinderhook (-1702)
	3817	Congl (-1733)
	3860	Reworked Arb (-1776)
	3870	Arbuckle (-1786)
	3904	R.T.D. 4 zones por in Arb
		D&A