


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - EL DORADO REFG. CO.,  
Farm - Fee No. 2

SEC. 34 T. 25 R. 5E  
SWc NW

Total Depth. 2444' PB to 2436'  
Comm. 6-7-47 Camp. 7-6-47  
Shot or Treated.  
Contractor. Cox & Burns  
Issued. 9-6-47

County. Butler  
KANSAS



CASING: 16" 23' 5 1/2" 2395'  
10 3/4" 913'  
8 5/8" 1716'

Elevation. \_\_\_\_\_  
Production. 10 Bbls.

Figures Indicate Bottom of Formations.

|                 |      |                            |                   |             |      |
|-----------------|------|----------------------------|-------------------|-------------|------|
| surface soil    | 10   | shale                      | 1025              | Tops        |      |
| lime            | 50   | lime                       | 1030              | Kansas City | 1945 |
| shale           | 90   | shale                      | 1040              | Arbuckle    | 2395 |
| lime            | 120  | lime                       | 1065              |             |      |
| shale           | 130  | shale                      | 1075              |             |      |
| red rock        | 135  | lime                       | 1100              |             |      |
| lime            | 145  | Gas                        | 1085              |             |      |
| shale           | 170  | shale                      | 1120              |             |      |
| lime            | 180  | lime                       | 1135              |             |      |
| shale           | 190  | shale                      | 1140              |             |      |
| lime            | 200  | lime                       | 1165              |             |      |
| shale           | 225  | Gas 1150-54                |                   |             |      |
| lime            | 230  | shale                      | 1170              |             |      |
| shale           | 275  | lime                       | 1185              |             |      |
| red rock        | 280  | shale                      | 1190              |             |      |
| lime            | 295  | lime                       | 1280              |             |      |
| shale           | 340  | 2 BWPB 1225-30             |                   |             |      |
| lime            | 345  | shale                      | 1335              |             |      |
| shale           | 355  | lime                       | 1380              |             |      |
| lime            | 390  | shale                      | 1385              |             |      |
| shale           | 405  | lime                       | 1410              |             |      |
| lime            | 415  | shale                      | 1470              |             |      |
| shale           | 470  | lime                       | 1475              |             |      |
| lime & shells   | 480  | shale                      | 1556              |             |      |
| shale           | 490  | lime                       | 1575              |             |      |
| sand            | 500  | Free Oil 1556-63           |                   |             |      |
| 6 BWPB 490-500  |      | red rock                   | 1580              |             |      |
| shale           | 510  | shale                      | 1585              |             |      |
| lime            | 515  | lime                       | 1590              |             |      |
| shale           | 520  | shale                      | 1650              |             |      |
| lime            | 525  | lime                       | 1790              |             |      |
| shale           | 535  | shale                      | 1945              |             |      |
| lime            | 555  | lime                       | 2045              |             |      |
| shale           | 580  | Oil Show 1960-65           |                   |             |      |
| lime            | 585  | shale                      | 2050              |             |      |
| Oil Show 580-85 |      | lime                       | 2097              |             |      |
| shale           | 590  | shale                      | 2170              |             |      |
| lime            | 605  | lime                       | 2180              |             |      |
| sand            | 610  | shale                      | 2220              |             |      |
| Oil Show 605-10 |      | lime                       | 2230              |             |      |
| lime            | 615  | shale                      | 2235              |             |      |
| shale           | 635  | lime                       | 2245              |             |      |
| lime            | 640  | shale                      | 2255              |             |      |
| shale           | 655  | lime                       | 2260              |             |      |
| lime            | 670  | shale                      | 2265              |             |      |
| shale           | 715  | lime                       | 2275              |             |      |
| lime            | 790  | shale                      | 2280              |             |      |
| shale           | 805  | lime                       | 2305              |             |      |
| lime            | 815  | shale                      | 2365              |             |      |
| shale           | 855  | lime                       | 2375              |             |      |
| sand            | 900  | shale                      | 2395              |             |      |
| HFW 855-80      |      | Free Oil 2400-05           |                   |             |      |
| shale           | 915  | lime                       | 2414              |             |      |
| lime            | 925  | shale green                | 2415              |             |      |
| shale           | 930  | lime                       | 2444-Wtr. 2441-44 |             |      |
| lime            | 940  | Total Depth                |                   |             |      |
| shale           | 950  |                            |                   |             |      |
| lime            | 965  | Hole Plugged back to 2436' |                   |             |      |
| shale           | 995  |                            |                   |             |      |
| lime            | 1005 |                            |                   |             |      |