

WELL LOG

6-16-24W
NE NE NE

COMPANY Thunderbird Drilling, Inc.

SEC. 6 T. 16S R. 24W

FARM Kaler

NO. 1

LOC. NE NE NE

RIG. NO. 3

API# 15-135-20,539 ✓

TOTAL DEPTH 4525


COMM. 3-6-72

COMP. 3-16-72

COUNTY Ness
KANSAS

CONTRACTOR

Rains & Williamson Oil Co., Inc.



CASING

20
15
12
1310
8
6
5

5/8" @ 330' w/ 200 sx. 2% gel, 3% cc.

ELEVATION 2448 KB

PRODUCTION DRY/MISS

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay	40
Shale	335
Shale and Sand	1235
Shale	1252
Blaine Anhydrite	1261
Shale	1385
Sand	1590
Shale and Red Bed	1870
Anhydrite	1905
Shale	2465
Shale and Lime	2715
Lime and Shale	3680
Lime	4400
Lime and Shale	4420
Lime	4525
Rotary Total Depth	4525

SAMPLE TOPS:

Anhydrite	1870
B "	1905
Heebner	3783
Toronto	3804
LKC	3824
BKC	4095
Marmaton	4133
Pawnee	4243
Ft Scott	4327
Cherokee	4355
" Sand	4414
Mississippi Lime	4422
" Dolomite	4512

DST (1)	4170-4230
DST (2)	4331-4350
DST (3)	4402-4420
DST (4)	4427-4464

