

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock,

Wichita, Kansas

16-16-24W


Company. THE OHIO OIL CO.
Farm. Lawrence Miller No. 1

SEC. 16 T. 16 R. 24W
C SE NE

Total Depth. 4625
Comm. 12-17-55 Comp. 1-13-56
Shot or Treated.
Contractor. H & H Drilling Co.
Issued. 2-11-56

County Ness

KANSAS



CASING:
10 3/4 368' w/ 300 sx cmt.

Elevation. 2530

Production. Dry

Figures indicate Bottom of Formations.

clay & sand streaks	155
sand & shale	300
shale	384
shale & shells	1255
shale & sand	1650
shale & shells	1715
lime & shale	1840
red bed & shale	1880
lime & shale	2880
lime	2935
lime & shale	3785
lime	3825
lime & shale	3925
lime	4213
lime & shale	4310
lime	4412
coring	4587
lime	4625
Total Depth	

SCOUT TOPS:

Heebner	3878
Toronto	3894
Lansing	3917
Ft. Scott	4420
Cherokee	4488
Mississippian	4526