


29-9-20 E
 SEC. 29 T. 9 R. 20 E.
 CNE NW

R. ANDERSON.
 Costigan No. 1.

County Jefferson.



Total Depth. 1434
 Comm. 11-12-41 Comp. 12-20-41
 Shot or Treated.
 Contractor.
 Issued. 2-21-42

CASING.

10" 71'
 8" 850'
 65/8" 1416' 1418

Elevation. 1029 Baptist

Production. 14,000,000
 cu ft gas.

Figures Indicate Bottom of Formations.

soil	1	shale	705
clay	4	lime	724
shelly lime	9	shale	824
sand	14	lime	826
shale blue	71	shale	829
lime	78	red rock	834
shale	83	lime	835
lime	90	shale	867
shale	92	lime	873
lime	105	shale	895
shale	108	lime	900
lime	111	shale	914
shale	122	lime	920
lime	129	shale dark	923
shale	150	lime	928
lime	153 3	shale dark	938
shale blue	225 7	lime	942
shale light	270	shale	963
red rock	275	lime	968
shale blue	390	shale dark	1050
lime	410	shale light	1120
shale dark	413	shale dark	1240
lime	418	shale light	1245
shale	437	shale dark	1355
lime	462 2 1/2 BWPB	shale sdy	1370
shale blue wtr	482	shale dark	1392
lime	495	siltstone	1397
shale blue	525	shale dark	1416
lime	542	Gas top. SLM 1420 * 1418	
shale blue	557	shale & sand ? 1434	
lime	562	Total Depth.	
shale dark	575		
lime	583	Top McLouth 1418	
shale	603		
lime	610		
shale	623		
lime	629		
shale water	633		
lime	665		
shale dark	675		
lime	700		