

10-16-5160


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HARMS-BURT DRILLING COMPANY &
Farm- SUNRAY MID-CONTINENT DRILLING COMPANY
Kendall No. 1

SEC. 10 T. 16 R. 21W
NW NW NE

Total Depth. 4301'
Comm. 3-19-56 Comp. 4-6-56
Shot or Treated.
Contractor.
Issued. 3-23-57

County Ness KANSAS



Elevation. 2337' RB

Production. Dry

CASING:

8 5/8" @230' w/200 sx cem.

Figures indicate Bottom of Formations.

Rock & clay	140
Clay & shale	175
shale	665
sand	750
shale w/sand streaks	1070
sand	1325
shale & red bed	1630
Anhydrite	1660
shale & red bed	1840
shale & shells	2045
lime & shale	2200
shale & shells	2375
lime	2465
lime, shale	2500
lime	2800
lime & shale	3605
lime	3635
shale & lime	3710
lime	4020
lime, shale & chert	4045
lime	4095
lime, shale, chert	4123
lime & shale	4230
lime, shale, chert	4285
lime & chert	4301
Total Depth	

DST #3 4242-4250 Op. 30 min.
shut in 20 min. Rec. 60' heavy
black oil & 1610' slightly oil
& gas cut wtr. IFP 400#,
FFP 950#, BHP 1210#.

RAN ELECTRIC LOG

TOPS

Anhydrite	1630
Heebner	3718
Lansing	3762
Fort Scott	4106
Cherokee Shale	4166
Mississippi chert	4270

DRILL STEM TESTS

DST #1 4197-4204 Op. 1 hr.
shut in 15 min. Rec. 390' wtr.
IFP 0# FFP 180#, BHP 590#.
DST #2 4215-4230 Op. 1/2 hr.
shut in 15 min. Rec. 2940' wtr.
IFP 510# FFP 1730# BHP 1260#.