

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PICKRELL DRIG. CO.

SEC. 11 T. 16 R. 21W  
 LOC. C SW SW

FARM Harms-Kendall "C" NO. 1

TOTAL DEPTH 4266'

COMM. 9-1-67

COMP. 9-11-67


SHOT OR TREATED

CONTRACTOR Pickrell Drig. Co.

ISSUED 12-30-67

COUNTY Ness

KANSAS



CASING

20	10	
15	8 5/8	245' w/160 sx cem.
12	6	
13	5 1/2	4261' w/125 sx cem.

ELEVATION 2270' KB

PRODUCTION Pmp 98 BOPD,  
 NW CHER 3264e65

FIGURES INDICATE BOTTOM OF FORMATIONS

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

980	Shale & Shells
1245	Sand
1554	Shale & Shells
1597	Anhydrite
2150	Shale & Shells
2285	Shale & Lime Streaks
2435	Lime & Shale
2800	Lime
3660	Lime & Shale
3755	Lime
3825	Lime & Shale
4091	Lime
4145	Lime, Sand & Chert
4158	Sand & Chert
4183	Sand
4205	Sand, Chert & Lime
4225	Sand & Chert
4265	Chert & Lime, RTD
4266	" " Total Depth

C. F. S.

3750'
4135'
4145'
4158'
4170'
4183'
4200'
4205'
4220'
4225'
4255'
4265'

Slope Tests

2500'
3000'
3500'
4000'

TOPS: SCOUT

Anhydrite	1555
Topeka	3382
Heebner	3661
Lausing	3705
Pawnee	4052
B/Pawnee	4115
1st Cherokee sand	4125
Mississippi	4214

S. L. M.

Board	3807.93
Strap	3805.19
Diff.	2.84 (No Correction)