

WICHITA BRANCH
KANSAS DRILLERS LOG

API No. 15

County

Number

Operator

PICKRELL DRILLING COMPANY

Address

205 LITWIN BLDG., WICHITA, KS. 67202

Well No.

6

Lease Name

BAER

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

PICKRELL DRILLING COMPANY

Geologist

KEN JOHNSON

Spud Date

5-25-78

Total Depth

4500

P.B.T.D.

Date Completed

6-20-78

Oil Purchaser

Clear Creek


S. 27 T. 16S R. 24W E

Loc. SW SW

County NESS

640 Acres

N



Locate well correctly

Elev.: Gr. 2527

DF 2529 KB 2532

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surf. casing		8 5/8		218		150	
Prod. casing		4 1/2		4499		150 50	50-50poz common

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP	4487-4490
			4	DP	4490-4493
			4	DP	4491-4494
Size	Setting depth	Packer set at			
2 3/8	4492				

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 6-22-78		Producing method (flowing, pumping, gas lift, etc.) Pumping		
RATE OF PRODUCTION PER 24 HOURS	Oil 30 bbls.	Gas MCF	Water trace bbls.	Gas-oil ratio CFPR
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 4490-4494	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator PICKRELL DRILLING COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE	
Well No. 6	Lease Name BAER		
S <u>27</u> T <u>16</u> S <u>R</u> <u>24</u> W ^E _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Top Soil & Sand	0	65	DST #1 4452-4490 30-30-10-out Wk. bloe died in 11", Rec. 5' mud, IFP 32-32 FFP 40-40 ISIP 53/30" FSIP NT
Post Rock-Shale	65	221	
Shale	221	300	
Shale & Sand	300	1183	
Shale & Sand	1183	1858	
Anhy.	1858	1885	DST #2 4490-4500 30-30-90-60 Strong blow, Rec. 120' GIP 700' Gsy Oil, 20' HOCM, IFP 64-96, FFP 161-247, ISIP 961/30" FSIP 993/60"
Anhy.	1885	1891	
Shale	1891	2300	
Shale & Lime	2300	2560	
Lime & Shale	2560	2765	
Lime & Shale	2765	2920	
Lime & Shale	2920	3100	
Shale & Lime	3100	3240	
Shale & Lime	3240	3395	
Lime & Shale	3395	3575	
Shale & Lime	3575	3780	
Shale & Lime	3780	3950	
Shale & Lime	3950	4100	
Lime	4100	4215	
Lime	4215	4320	
Lime & Shale	4320	4410	
Lime & Sand	4410	4490	
Sand	4490	4500	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 C. W. Sebits Partner Title August 8, 1978 Date		