

32-9-20E


LONGWELL ET AL
Brose No. 1.

SEC. 32 T. 9 R. 20 E
CNW SE

DEEPENING RECORD

Total Depth. 1552'
Comm. 8-29-41 Comp. 9-20-41
Shot or Treated.
Contractor. Wilson
Issued. 12-25-43

County. Jefferson



CASING:
10" 86'
8 1/2" 944'
6 5/8" none
53/16" 1489' Cem.

Elevation. 1152

Production. 3,360,000 Gas

Figures Indicate Bottom of Formations.

clay	15-32	shale dk	802
gravel	35	lime	829
mud	80	shale	833
lime	90	lime & shale	860
shale blue	141	shale lgt	900
lime	144	shale 16 BWPB	937
shale dk	150	shale	970
lime	152	lime	975
shale dk	155	shale	1011
shale	175	lime	1014
lime	185	shale	1022
shale	187	lime	1028
lime	216	shale	1048
shale	225	lime	1054
lime	234	shale	1057
shale	260	lime	1060
shale green	265	shale	1150
lime	275	lime sholls	1153
shale lgt	285	shale	1170
shale sdy	303	sand	1175
shale	428	shale dk	1185
shale lgt	440	shale lgt	1199
shale gy	470	shale	1240
shale	500	red	1248
lime	506	shale	1262
shale lgt	509	sand	1272
lime	520	shale dk	1294
shale	540	lime	1296
lime	550	sand	1304
shale	555	shale lgt	1314
lime	568	shale dk	1324
shale	590	shale lgt	1339
lime	592	shale dk	1348
shale	594	shale	1443
lime	600	shale sdy	1461
shale	603	lime	1463
lime	605	shale lgt	1470
shale lgt	633	shale dk	1480
limo	643	shale sdy	1485
shale	648	1485 equals 1498 SIM	
lime	653	gas sand	1502
shale	667	shale	1505
limo	670	gas sand	1506
shale	675	shale	1510
lime	690	gas sand	1517
shale	706	oil sand	1518
lime	716	Total Depth.	
shale lgt	721		
shale dk	727		
lime	750		
shale	755		
limo	778		
shale lgt	786		
lime	788		
shale	790		
lime	801		

DEEPENING RECORD:

Comm. 10-19-43
Comp. 10-28-43
Production - Dry
Contractor - Soup McKimney

sand 1520
lime 1521
shale 1533
lime 1539
shale lt 1540
lime 1542
lime 1552
Total Depth.

Miss. lime was dry
T. Miss. 1533
gas at 1550