


KANSAS DRILLERS LOG

API No. 15 — 035 — 21,823
County NumberS. 11 T. 32 R. 4 E
W

Loc. _____

County Cowley

640 Acres
N

Locate well correctly

Elev.: Gr. 1212

DF 1215 KB 1217

Operator

Aladdin Petroleum Corporation

Address

809 Petroleum Bldg., Wichita, KS 67202

Well No.

1

Lease Name

Dicken

Footage Location

330 feet from (N) X line 1320 feet from (W) line of SE/4

Principal Contractor

White & Ellis Drilling Co.

Geologist

George R. McNeish

Spud Date

2-10-78

Total Depth

3510

P.B.T.D.

Date Completed

3-17-78

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8"	24#	215	Posmix	85	
Production	7-7/8"	5-1/2"	14#	3508	Posmix	275	18# salt p. sack

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	SDJ	3458-1/2-59-1/2
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 3-17-78		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil 30 bbls.	Gas MCF	Water 200 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) -			Producing interval (s) 3458-1/2 - 3459-1/2		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Aladdin Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Dicken	Oil
S 11 T 32 R 4 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Cellar	0	7	Stalnaker	1936
Shale & Lime (Stks)	7	313	Layton Sd.	2337
Shale & Lime	313	839	KC. Lime	2468
Shale & Lime (Stks)	839	2113	Base KC	2612
Shale & Lime	2113	2298	Cherokee	2825
Shale & Sand	2298	2417	Mississippi	3039
Shale & Lime	2417	2470	Chattanooga	3390
Lime	2470	2614	Arbuckle	3458
Sandy Shale	2614	2834		
Shale & Lime	2834	3022		
Shale	3022	3040		
Lime	3040	3510		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>F. J. Marshall</i> Signature <i>Geologist</i> Title <i>6-28-78</i> Date
---------------	---

11-27-82

State Geological Survey
WICHITA BRANCH

DRILLERS LOG

15-035-21823
11-32-4E

OPERATOR: Aladdin Petroleum Corporation; 809 Petroleum Bldg.; Wichita, KS
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042 67202

Lease Name Dicken Well No. 1
Sec. 11 T. 32S R. 4E Spot Cen. N Line SE 1/4
County Cowley State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 201' with 85 Sxs.

Production: 5 1/2" @ 3508' with 250 Sxs.

Type Well: Oil Total Depth 3510' K.B.

Drilling Commenced: 2-10-78 Drilling Completed 2-21-78

Formation	From	To	Tops
Cellar	0	7	Kansas City 2470
Shale & Lime (Stks)	7	313	Mississippi 3040
Shale & Lime	313	839	Arbuckle 3474
Shale & Lime (Stks)	839	2113	
Shale & Lime	2113	2298	
Shale & Sand	2298	2417	
Shale & Lime	2417	2470	
Lime	2470	2614	
Sandy Shale	2614	2834	
Shale & Lime	2834	3022	
Shale	3022	3040	
Lime	3040	3510	