

State Kansas County Barber


Company Senclair Oil & G. Co. Well No. _____

Farm Welsh "B"

Survey _____

Block No. _____ Sec. 8 Twp. 32^e Range 15^w

Co-Ord. _____ Elev. _____



of
Welsh Ranch Property

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
<u>4-7-60</u>	<u>4758</u>	<u>Miss. Chat (-2830)</u>
<u>D.S.J. #1</u>	<u>- 4753-76</u>	<u>- Op. 1 hr.</u>
		<u>G.S. in 1" Rec 90' gent.</u>
		<u>ba. 360.500 ft. finished</u>
		<u>(Go drill 20' & test)</u>

715436

Date

Depth

7" - 179,000 cfb.

15" - 249,000 cfb.

30" - 313,000 cfb.

(stabilized) 45" - 361,000 cfb.

B.H.P. - 1755-1755[#]I.P. - 32-70[#]

D.S.J. #2 - 4776-4810 - op. 1 hr.,

wb. bl. Rec. 20' mud,

B.H.P. - 440-135[#]I.P. - 35-35[#]

5-9 - D.S.J. #3 - 4837-76 - op. 1 hr.,

wb. bl. Rec. 40' mud,

B.H.P. - 1520-153[#]I.P. - 25-50[#]

4880 Only. (20' net pay)

5-10 4925 R.J.W. (Running Elev. Log)

4 1/2" @ 4925'

5-17-60

P.B. to 4885'

Row Gamma Ray section

Prof. 4761-84 w/92^s

Treated 500 m.a.

To test + acid petro-fro

Rec. 18 bbls. acid wtr.

no new water.

op. 35 580[#] Ibg. 200[#]
Ibg. 60-81 Mibg. Log. 250[#] Ibg. 40[#]

