

DEC 20 1969

ROTARY DRILLING LOG

Operator: Beardmore Oil Inc.
ALBERS "B" #1
SE SW Section 34-16S-24W
Ness County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 10-27-69
Completed: 11-7-69
Casing: 8-5/8"/218'/160' sx.
common cement

Formations

Shale	222'
Shale and Sand	1203'
Blaine Anhydrite	1211'
Shale and Sand	1565'
Red Bed	1805'
Shale	1830'
Anhydrite	1858'
Shale	2055'
Shale and Lime	2550'
Lime and Shale	2734'
Lime	3460'
Lime and Shale	3852'
Lime	4415'
Lime and Chert	4487'
Lime	4508'
Rotary Total Depth (D & A)	4508'

Dry
elv. 2512' KB

Cores:

None

Drill Stem Tests:

1
4432-87/op 60 min.
Rec. 5' M
IBHP - 62/30
FBHP 52/30
FP 41 - 41#

2 (straddle test)
4260-83/op 60 min.
Wk blow - 25 min.
Rec. 5' 0 spkd M
IBHP - 41#/30 min.
FBHP 41#/30 min.
FP 31-31#

*g is
best
lief.*

CO., INC.

3
4489-4508/op 9 min.
Rec. 5' Oil 130' mdy W.
IBHP - 1225/45
FBHP 1173/60
FP 83-104#

Log Tops:

Anhydrite	1829' (+ 683)
Heebner	3851 (-1339)
Lansing	3893 (-1381)
Base of K.C.	(-1671)
Pawnee lime	4308 (-1796)
Fort Scott	4390 (-1878)
Cherokee	4414 (-1902)
Base of Cherokee lm.	4456 (-1944)
Mississippian	4478 (-1966)
TD	4508 (-1996)

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 10 day of November, 1969.

Sherry Gish
Sherry Gish Notary Public