


State Kansas County Barber
 Company Petroleum, Inc Well No. 1
 Farm Hall "2"
 Survey _____
 Block No. _____ Sec. 36 Twp. 33 S Range 13 W
 Co-Ord. _____ Elev. 1509



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
	3536	Elgin (-2027)
	Net 3538-10,	op 30". Rec 10' mud.
	3720	Heebner (-2211)
	3820	Doug Sd (-2311)
	3906	Lans (-2397)
	4385	B/K.C. (-2876)
	4538	Miss Chest (-3029)
	Net 4540-55,	op 1 hr. gas in 55".
		Rec. 105' gcm shp 1350/30"

Date

Depth

715491

Set 4556-75, op 15". Gas in 1 1/2".

3,500,000 cf/15" BHP-1675⁺/45'

Set 4576-4600, op 14". Gas in 1".

4,640,000 cf. BHP 1700⁺/45'

4593 Miss Low (-3084)

4640 RSD 4 1/2" @ 4637

Cleaned out to 4598

Perf 4570-80 and 4546-62 w/140^S

gauged 3 1/2 mil, natural.

500 gals MCA

1500 pet pres & 15000⁺ sh.

gauged 8,268,000 cf 3/4" choke

tby pres 700⁺cog pres 1380⁺