

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas


34-16-24W

Company. BARNETT OIL CO.  
Farm. Albers No. 1

SEC. 34 T. 16 R. 24W  
C NW SW

Total Depth. 4534 (4523)  
Comm. 10-26-63 Comp. 11-9-63  
Shot or Treated.  
Contractor. 3 Gabbert-Jones Inc.  
Issued. 3-7-64

County Ness  
KANSAS



Elevation. 2534' KB

Production. Dry

CASING:

8 5/8" 215 1/2' cem w/175 sx.  
5 1/2" 4514' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface clay, sand & shale	216
shale	290
shale, redbed	770
sand	890
shale w/sand	1280
shale, redbed	1650
shale & shells	1865
Anhydrite	1900
shale & shells	2535
lime & shale	2770
lime	3041
lime & shale	3808
lime	4367
lime & shale	4500
lime	4534
Total Depth	

TOPS: LOG

Heebner	3873
Lansing	3915
Base Kansas City	4215
Marmaton	4263
Ft. Scott	4409
Cherokee Zone (sample)	4479
Cherokee Sand	4497
Mississippi	4512