


A.S.B. PIPELINE CO.
 -Edwards No. 1.
 Edmonds.

SEC. 34 T. 9 R. 20E.
 CSW SW
 660' to SL 600' to WL SW 1/4
34-9-20E
 County Leavenworth.

Total Depth. 1447 1/2
 Comm. 6-30-41 Comp. 7-26-41
 Shot or Treated.
 Contractor. Olie Barny
 Issued. 8-9-41

Plotted



CASING.

8 1/4" 875'
 53/16" 1395'

Elevation. 1071 *Guess*

Production. ~~1,800 M~~
 2,700,000 cu. ft. gas

Figures Indicate Bottom of Formations.

dirt	15	limo	875
lime	17	shale blue	880
shale	37	limo grey	883
lime	40	shale blue	887
shale	60	limo	891
lime	75	shale white	908
shale	80	shale blue	915
lime	95	lime	920
shale	99	limo	928 <i>ch</i>
lime	105	shale	970
shale	110	shale blue	1015
lime	120 <i>MA</i>	limo	1020
shale	140	sdv shale	1035
shale	250	shale dark	1050
shale	260	limo	1054
red rock	265	shale dark	1065
shale	375	shale white	1110
shale dark	390 <i>L</i>	shale	1165
lime light	415	shale	1175
shale dark	419	shale	1215
lime grey	425	red rock	1220
shale dark	432	shale	1235
lime grey	460	shale	1265
shale light	485	shale blue	1310
lime	500	sdv blue shale	1330
shale dark	525	shale dark	1370
lime gy	540	shale light	1380
shale blue	555	shale light	1393
lime grey	570	gas sand	1394
shale blue	575	1394-97 SLM	
lime grey	585	sand	1411
shale blue	595	sand	1417
lime grey	605	sand sat. oil	1419
shale dark	620	shale dark	1423
lime	628	shale light	1424
shale	630	shale light	1425
lime grey	660	sand	1430
lime brown	675	shale	1436
slate blk	680	sdv shale	1440
lime grey	685	sdv shale light	1444 <i>M</i>
lime brown	700	lime	1447 1/2
wtr 705		Total Depth.	
lime grey	715 <i>BKC</i>		
shale	760?		
shale blue	810 711 SLM	Test	1411- 2,120 MF.
shale blue	820		1419- 1,800 M
shale light	830		
shale blue	850		
shale white	865		
shale	870		