


Plotted

35-9-20E

Total Depth. 1550'
 Comm. 5-11-44 Comp. 5-31-44
 Shot or Treated.
 Contractor. John Schafges
 Issued. 6-24-44

County. Leavenworth
 KANSAS



CASING:
 10" 65
 8 1/4" 774
 6 5/8" 1396

Elevation. 998 Dan

Production. Dry

Figures Indicate Bottom of Formations.

soil	2
clay	12
lime sand rock	35
shale	42
lime	50
shale	325
lime	330
shale	335
lime	351
shale	355
lime	360
shale	375
lime	390
shale	420
lime	428
shale	465
lime	483
shale	493
lime	500
shale	510
lime	523
shale	535
lime	545
shale	560
lime	565
shale	571
lime	603
shale	612
lime <i>15 BPH 612-17</i>	654
shale	775
red shale	780
shale	803
lime	808
shale	825
lime	830
shale	850
lime	860
shale	865
lime	870
shale	890
lime	893
shale	1160
sand <i>2 1/2 BW</i>	1175
shale	1365
sand brkn	1375
shale	1388
lime Miss.	1410
shale	1420
lime	1550
Total Depth.	

Top Miss. Lime 1388

1BWPH 1465-70
 sh oil 1548-50