

34-16-24W


COMPANY PICKRELL DRLG. CO.

SEC. 34 T. 16 R. 24W  
 LOC. C SE SE

FARM Horchem "E" NO. 1

TOTAL DEPTH 4498'  
 COMM. 4-24-67 COMP. 5-4-67  
 SHOT OR TREATED  
 CONTRACTOR Pickrell Drlg. Co.  
 ISSUED 8-12-67

COUNTY Ness  
 KANSAS



CASING

20	10	
15	8 5/8	277' w/170 sx cem.
12	6	
13	5 1/2	4486' w/160 sx cem.

ELEVATION 2524' KB

PRODUCTION Pmp 82 BOPD  
 & 6% W./Miss 4486-4500  
 Grav. 37

FIGURES INDICATE BOTTOM OF FORMATIONS

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

277	Shale & Shells
600	Shale
1100	Shale & Shells
1200	Shale & Red Beds
1211	Blaine
1280	Red Beds & Shale
1565	Sand
1835	Shale & Shells
1867	Anhydrite
2890	Lime & Shale
3005	Lime
3945	Lime & Shale
4183	Lime
4455	Lime & Shale
4475	Lime, Shale & Sand
4485	Lime & Shale
4489	Lime, Shale & Sand
4500	Mississippian, RTD
4498	Log Total Depth

C. F. S.

4265  
 4267  
 4402  
 4422  
 4465  
 4475  
 4485  
 4500

Slope Tests

3000  
 3500  
 4000  
 4500

TOPS: SCOUT

Anhydrite	1824
Heebner	3852
Lansing Kansas City	3897
Marmaton	4252
Pawnee	4308
Ft. Scott	4390
Cherokee	4414
Cherokee sand	4460
Warsaw	4484

S. L. M.

3987