

35-16-24W

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
308 EAST MURDOCK - WICHITA, KANSAS

COMPANY BEARDMORE DRILLING

SEC. 35 T. 16 N. 24W  
LOC. C SW SW

FARM Horchem

NO. 1

COUNTY Ness

TOTAL DEPTH 4507

COMM. 1-12-67


COMP. 1-23-67

SHOT OR TREATED

CONTRACTOR Sterling Drlg.

ISSUED 4-1-67

KANSAS



CASING

20	10	
15	8	5/8" @ 214' w/175 sx
12	6	
13	5 1/2"	@ 4494' w/100 sx

ELEVATION 2528' KB

PRODUCTION PMP 70 BOPD &  
36 % Wtr/MISS 4494-4508

FIGURES INDICATE BOTTOM OF FORMATIONS

LOG

CASING RECORD

0 - 216	Sand, Clay & Shale
216 - 1838	Shale & Sand
1838 - 1845	Anhydrite
1845 - 1960	Anhydrite & Shale
1960 - 3030	Lime & Shale
3030 - 3263	Shale
3263 - 3975	Shale & Lime
3975 - 4507	Lime T.D.

Run 10 joints (202') 8-5/8" casing,  
pipe set st 214' K.B. with 175 sacks  
common cement. Plug was down at  
1:30 a.m..

Run 145 joints 5-1/2" 15.5# seamless  
casing, 4524' pipe set at 4494' K.B.,  
cemented with 100 sacks regular cement.  
Plug was down at 7:00 p.m. 1-23-67 by  
Globe.

E-log tops:

Blaine	1206
Stone Corral Anhy.	1839
Heebner	3864
Lansing	3909
Base Kansas City	4198
Marmaton lm.	4260
Pawnee	4317
Fort Scott	4400
Cherokee shale	4421
Miss. dolo.	4480
TD	4508

DST

No. 1	4484-4492
No. 2	4493-4507
<u>Cores</u>	
No. 1	4492-4507 Rec. 15'