

PIERPONT # 42.

Sec. 33 - Town. 25 - R. 5 - Butler County, Kansas.

Location

990' south and 330'  
east from the NW corner of  
the SW $\frac{1}{4}$  of the section.

Sand record.

612' - 624' - 12'  
2471' - 2484' - 13'

Drilling commenced Feb. 18, 1918.  
Drilling completed April 11, 1918.

Casing record.

12 $\frac{1}{2}$ " 895' pulled out.  
10" 935'  
8 $\frac{1}{2}$ " 1647'  
6 5/8" 2471'  
2" 2492'

Total depth of well 2484'.

Production 10 bbls. 1st 4 hrs.

Surface	5	5
lime	50	55
shale	15	70
lime	16	80
red rock	6	86
slate & shells	40	126
slate & shells	20	146
red rock	4	150
lime	5	155
slate	20	175
lime	10	185
slate	15	200
slate	30	230
lime	10	240
slate	15	255
slate	25	280
red rock	5	285
lime	15	300
slate & shells	60	360
slate & shells	70	430
lime	20	450
slate	50	500
slate	30	530
lime	20	550
shells	10	560
red rock	5	565
lime	10	575
slate	25	600
slate	12	612
sand	12	624
slate	30	654
lime	10	664
slate	30	694
lime	6	700
slate	20	720
lime	30	750
slate	10	760
lime	40	800
lime	20	820

Water 530' 8 bailers water

Oil 612' 2 bailers hr.

Hole full water

PIERPONT # 42, - PAGE 2.

slate	10	830	
slate	5	835	
sand	40	895	Water sand cased 12 $\frac{1}{2}$ "
slate	45	938	Cased in at 935
slate	10	945	
lime	30	975	
slate	55	1030	
slate	15	1045	
lime	45	1090	
slate & lime	82	1192	Gas 1172' to 1176'
lime	4	1176	
slate	10	1186	
lime	20	1205	
slate & shells	15	1220	2 bailers 1215'
lime	60	1280	
slate	35	1315	
lime	10	1325	
slate	105	1430	
sand	80	1510	
slate	10	1520	12 bailers water per hr at 1520'
slate	35	1555	Hole full of water.
slate	10	1565	
lime	5	1570	
slate	25	1595	
lime	20	1605	
slate	25	1640	
slate	7	1647	Cased 8 $\frac{1}{2}$ "
slate	48	1695	
lime	40	1735	6 bailers water per hr. at 1735'
lime	45	1780	
lime	30	1810	
lime	15	1825	
slate	133	1958	
lime	27	1985	
lime	15	2000	
lime	35	2035	
lime	10	2045	
slate	6	2051	
lime	20	2071	
lime	47	2118	
slate	72	2180	
lime	10	2190	Cave
slate	20	2210	
lime	20	2230	
slate	30	2260	
lime	15	2275	
slate	10	2285	
lime	10	2295	
slate	95	2390	
red rock	5	2395	
slate	70	2460	
sand		2460	
run steel line		2471	
sand	13	2484	