

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

10-16-25W


Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Giess "B" No. 1

SEC. 10 T. 16 R. 25W
C SW NW

Total Depth. 4510'
Comm. 4-3-61 Comp. 4-15-61
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.
Issued. 7-29-61

County Ness

KANSAS



CASING:
8 5/8" 252' cem w/175 sx.
5 1/2" 4504' cem w/125 sx.

Elevation. 2555' DE

Production. 201 BOPD - 5% water

Figures Indicate Bottom of Formations.

clay & sand	110
shale	365
shale & shells	665
sand	995
shale & shells	1349
Anhydrite (Blaine)	1362
sand & shale	1700
red bed	1958
Stone Corral Anhydrite	1992
red bed & shale	2085
shale & shells	2545
lime & shale	2995
shale	3050
shale & lime	3835
lime	3910
lime & shale	3963
lime & chert	4030
lime	4485
lime & chert	4495
lime	4507 RTD
Total Depth lime	4510

TOPS:
Anhydrite 1958
Heebner 3858
Toronto 3874
Lansing 3896
Ft. Scott (Cher) 4402
Mississippi 4502

DST #1 4058-80', op 1 hr, rec. 120' mud.
BHP 1240# to 1130#/15 mins.

DST #2 4405-40', op 1 hr, rec. 40' oil
cut mud & 60' muddy oil. BHP 1230# to 1060#.

DST #3 4472-4507', op 90 mins, rec. 190'
oil cut mud. BHP 1200#-1120#.