

15-135-21457

10-16-25W

D R I L L I N G L O G

#1 Geiss

7 jts. 8-5/8"
surface casingCOMPANY: Jim Thompson and
 Dean Allison
CONTRACTOR: Strata Drilling CompanyDESCRIPTION: C W/2 NE SE
 Section 10-16S-25W
 Ness County, KansasTOTAL ROTARY
DEPTH: 4538'

COMMENCED: May 5, 1978

COMPLETED: May 12, 1978

FORMATIONFROMTOREMARKSSurface soil and sand
Shale and sand
Anhydrite
Shale
Lime and Shale
Lime
Lime and shale0 300
300 1953
1953 1990
1990 2060
2060 4270
4270 4400
4400 4538Ran 286' used 8-5/8" surface casing;
set and cemented @ 291' with 185 sacks
common cement, 2% gel, 3% C.C. Cement
circulated. Plug down @ 8:15 p.m.,
May 6, 1978.

Ran one drill stem test.

Ran one electric log.

Ran 116 jts. new 4½" casing; set and
cemented @ 4535' with 100 sacks 50-50
Pozmix, salt saturated. Plug down
9:05 a.m., May 12, 1978.STATE OF KANSAS)
)ss
COUNTY OF BARTON)I certify that this is a true and correct copy of the above log to the best
of my knowledge.

STRATA DRILLING COMPANY

Kenneth L. Link