

PI
me

State Geological Survey
WICHITA BRANCH

10-16-25W

SEP

D R I L L E R S L O G

#3 Jarvis

CASING RECORD:
8 jts. new 24#
8-5/8" surface
casing

COMPANY: Okmar Oil Company

CONTRACTOR: Strata Drilling Rig #1-
Beredco, Inc.

DESCRIPTION: S/2 SW NE
Section 10-16S-25W
Ness County, Kansas

TOTAL ROTARY
DEPTH: 4529'

COMMENCED: May 15, 1981

COMPLETED: May 23, 1981

ELEVATION: 2580' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, sand. lime	0	332	Ran 323' new 24# 8-5/8" surface casing; set and cemented at 328' with 200 sacks 60-40 pozmix, 2% gel, 3% C.C. Cement circulated. Plug down at 9:30 p.m., May 15, 1981.
Shale, sand and shale	332	1963	
Anhydrite	1963	1998	
Shale	1998	2840	
Lime and shale	2840	4280	
Lime	4280	4385	Ran 4 drill stem tests.
Lime and shale	4385	4444	
Lime	4444	4529	
			Ran 1 electric log.
			Ran 107 jts. new 5½" casing; set at 4515' with 200 sacks 60-40 pozmix, 10% salt. D-V Tool set at 1947' with 350 sacks Halliburton Light, 50 sacks common. Job completed at 7:15 a.m., May 23, 1981.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the
best of my knowledge.

STRATA DRILLING RIG #1 - BEREDCO, INC.

Charles W. Steincamp
Charles W. Steincamp