

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- CITIES SERVICE OIL CO.
Farm- Pierpont No. 1-S

SEC. 33 T. 25 R. 5E

SE NE NW NW
400' S, 1370' W. of N $\frac{1}{2}$ Corner

County Butler

KANSAS



Total Depth. 3096

Comm. 7-23-52

Comp. 8-24-52

Shot or Treated.

Contractor. B. & R. Drlg. Inc. & Chet Myers

Issued. 11-1-52

Elevation. 1385 R.T.B.

Production. Water Supply

CASING:

13" 63' cem. w/100 sx
8 5/8" 2405' cem. w/250 sx

Figures Indicate Bottom of Formations.

soil	3	2404-08' lt stain
lime & shale	467	2408-10' S.O.
shale & lime & sand	1215	2410-29' G.S.O.
lime & shale	1678	2429-45' G.S.O.
lime	1795	2445-50' N.S.O.
lime & shale	2396	2450-55' F.S.O.
lime cherty	2508	2455-59' N.S.O.
lime	2704	2459-65' F.S.O.
lime & chert	2826	2465-79' N.S.O.
lime	RTD 3096	2479-2527' N.S.O.
Total Depth		2527-32' S.S.O. ?
		2532-46' N.S.O.
Tops:		2546-59' S.S.O. ??
Top 700' Sand 620'		2559-74' N.S.O.
Base	637	2574-90' F.S.O.
Douglas Sand	1473	2590-3076' N.S.O.
Base	1506	3076-96' N.S.O.
Iatan Lime	1572	R.T.D. 3096
Base	1590	Ran Electric survey log &
Lansing Lime	1665	Microlog from T.D. to
Base	1807	surface reamed to 2405'
Kansas City Lime	1954	set oil string Moved in
Base	2108	cable tools drld cement
Erosional Simpson	2385	plug & C.O. to 3096'
Base	2404	Filled up 2596' water
Arbuckle Lime	2404	Set Reda pump.
Base Arbuckle	3076	Completed for a combination
Granite Wash	3076	oil & water supply well.

Steel Line Measurement:

438=437
1015=1017
1505=1506
2024=2024
2365=2365
2405=2405
2530=2530
1790=1765
2704=2705
2944=2940
3000=3000
2059=2058
2395=2395

Note: All measurements taken from R.T.B.

I.P: App. 3600 bbls water, natural with Reda Pump.

620' F.S.O.
1473' N.S.O.
1572-90' F.S.O.
1607-19' lt. oil stain?
1683-90 F.S.O.
1707-33 F.S.O.
1960-66' G.S.O.
1966-1981 F.S.O.
2016-24' lt. oil stain
2075-37' S.S.O.
2385-2402' N.S.O.
2402-04 G.S.O.