

JAN 31 1970

DRILLERS LOG

#1 Kaler

11-16-25W
C NW NE

CASING RECORD:
310' of used 8-5/8"
surface casing.

COMPANY: Okmar Oil Company
CONTRACTOR: Strata Drilling, Inc.
COMMENCED: October 17, 1969
COMPLETED: October 28, 1969


ELEVATION: 2515' KB
DESCRIPTION: C/NW/4 NE/4
Section 11-16S-25W
Ness County, Kansas

TOTAL DEPTH:
4489'

ELV 2517 KB
36 BOPD

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Sand & Shale	0	343	Ran 310' of used 8-5/8" surface casing; set and cemented at 310' with 170 sacks of regular cement, 2% gel and 3% C. C. Plug down at 11:58 P. M. October 18, 1969.
Shale & Shells	343	750	
Shells, Shale & Red Bed	750	805	
Dakota Sand	805	870	
Shells & Shale	870	1020	
Anhydrite	1020	1030	
Blue Shale & Red Bed	1030	1302	
Anhydrite	1302	1328	
Red Bed, Shale & Shells	1328	1343	
Shale	1343	1380	
Sand	1380	1600	
Shale	1600	1910	
Anhydrite	1910	1921	
Anhydrite	1921	1944	
Shale & Shells	1944	2090	
Shale, Shells & Red Bed	2090	2562	
Lime & Shale	2562	3544	
Lime	3544	3714	
Lime & Shale	3714	4053	
Lime	4053	4489	

Total Depth 4489'



52' casing set and cemented at 4478' with 125 sacks of cement.

Blaine 1302
Anhydrite 1910
Hebner 3821
Lansing 3864
Lawrence 4286
Z. J. Scott 4366
Mississippi 4469