

MAR 13 1971

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

11-16-25W
NW NE NE
Elev. 2507 KB

KALER #5
NW NE NE Section 11-168-25W
Ness County, Kansas

Commenced: December 15, 1970
Completed: December 23, 1970

(WAS ABAND. LOC.)
11-19-70

OPERATOR - Okmar Oil Company

P 101 BOPD n/w

DEPTH	FORMATION	REMARKS
From	To	
0	290	Shale and sand Ran 8 joints of 8-5/8" casing, set @ 290 w/200 sacks cement.
290	1050	Shale
1050	1720	Shale and sand <i>Sample left</i>
1720	1904	Shale
1904	1939	Anhydrite
1939	2527	Shale
2527	2755	Shale and lime
2755	2847	Lime
2847	3180	Lime and shale
3180	3320	Lime
3320	3620	Lime and shale
3620	3788	Lime
3788	4040	Lime and shale
4040	4300	Lime
4300	4470	Lime and shale
4470	4480	Lime
4480	TD	Ran 143 joints of 5-1/2" casing, set @ 4472' w/100 sacks cement.

Lansing 3857
Garrett 4279
F + Scott 4360
Mississippi 4471

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the S/2 SW NW Section 21-145-14W, Russell County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 28 day of December, 1970, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
Barbara J. Layton, Notary Public