

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


34-16-23W

Company- IMPERIAL OIL CO.
 Farm- Schreiber No. 1

SEC. 34 T. 16 R. 23W
 C NW NW

Total Depth. 4501'
 Comm. 4-9-63 Comp. 4-23-63
 Shot or Treated.
 Contractor.
 Issued. 7-20-63

County Ness
 KANSAS



CASING:
 8 5/8" 318' cem w/200 sx.

Elevation. 2476' KB

Production. Dry

Figures Indicate Bottom of Formations.

sand & clay	317
shale	950
shale & sand	1315
Dakota Sand	1515
shale & red bed	1805
Anhydrite	1839
shale & shells	2440
shale & lime	3436
lime & chalk	3740
lime & shale	3863
lime	4070
lime & chert	4112
lime	4501 RTD
Total Depth	

TOPS:	SAMPLE	ELEC.
Anhydrite	1805	1804
Base Anhydrite	1839	
Heebner	3855	3853
Toronto	3873	3871
Lansing	3892	3887
Base Kansas City	4174	4172
Fort Scott	4272	4272
Cherokee Shale	4359	4358
Warsaw	4455	4449
Osage	4466	4468

DST #1 4356-95' op 35 min. Weak blow;
 died in 5 min. Rec. 10' of oil specked
 mud. IBHP 1309#, IF 37#, FF 37#, FBHP
 178# in 30 min.

DST #2 4454-66' op 30 min. Weak blow.
 Dead in 1 min. Rec. 3' of oil specked
 mud. IBHP 783#, IF & FF zero, FBHP 74#/
 30 min.

DST #3 4462-74' op 30 min. Reco. 10'
 of drilling mud. IBHP 1422, IF 14, FF
 20, FBHP 1120/30min.

DST #4 4470-82' op 2 hrs. Rec. 722' of
 salt wtr. IBHP 1324, IF 22, FF 335, FBHP
 1324#/30 min.