

State Kansas County Rush
Company Natural Gas & Oil Co Well No. 1
Farm Morrow
Survey _____

Block No. _____ Sec. 31 Twp. 17 Range 20W

Co-Ord. _____ Elev. 2177 KB

SE SW NE

Rig#2 2175 DF

100% Natural Gas & Oil Co.
Contract

4250' - Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

2310 Ft. from N. Line Ft. from S. Line

Ft. from W. Line 1650 Ft. from E. Line

Date	Depth	
11-5-56		MIRT
11-6-56		Spud; Set 8 5/8" @ 500' w/275
		sx. cem. 5 gal 3 cc P.D 6:30
		P.M. Under surf. tonight @
		6:40 P.M.
11-8-56	1615'	Drlg. Anhydrite 1404-51(+773
		No elevation yet.
11-9-56	2435'	Drlg.
11-12-56	3375'	Drlg.

Date	Depth	715892
11-13-56	3603'	Drlg.
11-14-56	3791'	Drlg.
11-15-56	3881'	Drlg. Had come in hole
11-16-56	4013'	Drlg. Will core tomorrow
		Running high to 2 dry holes.
11-9-56	4118'	Drlg.
	DST No. 1	4086-4104 op. 1 hr. SI/15" rec. 2065' SO & GCSW, FP 0-1240# BHP 1280#
	DST No. 2	4139-48 op. 1 hr SI/15" rec. 70' drlg. mud. FP 0-0# BHP 1080#
	<u>Core:</u>	4084-4104 19'7" rec.
11-20-56	4195'	TD
	DST No. 3	4180-95 op. 1 hr SI/15" rec. 405' SW, FP 100-260# BHP 1100# Plugged & abandoned 11-20-56
	<u>Sample Tops:</u>	Heebner 3576 (-1399)
		Lans. 3620 (-1443)
		B/Kc 3918 (-1741)
		Ft. Scott 4075 (-1898)
		Cherokee 4080 (-1903)
		Miss. 4154 (-1977)