


WELL RECORD

15-16-25W

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)

API# 15-135-20660

L



Locate well correctly

Lease Name: Huxman Well No. 1  
 Well Located: C E/2 NE/4  
SEC 15 TWP 16S RGE 25W  
 Operator: Vincent Oil Corporation  
 Address: 719 Union Center, Wichita, Kansas 67202  
 Elevation: Ground 2567 D.F. 2573 K.B. 2575  
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: August 9, 1972 Drilling Completed: August 19, 1972  
 Well Completed: 19 Total Depth 4543'  
 Initial Production: D&A

Casing Record

Size: 8-5/8" Set at 276' Size: \_\_\_\_\_ Set at \_\_\_\_\_  
 Set 7 joints of 8-5/8" surface casing at 276' G.L. w/200 sx. cement. Cement circulated.  
 Plug was down at 6:45 p.m. 8-9-72.

Dry and Abandoned  
liner Record

Size: \_\_\_\_\_ Set from \_\_\_\_\_ To \_\_\_\_\_

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8-5/8"</u>	<u>200</u>	<u>Sunset</u>
_____	_____	_____
_____	_____	_____

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
_____	_____
_____	_____
_____	_____

Electric Log Run. (Show type log and depths covered)

None

(Fill in formation and related information on reverse side)

1546-250

Show Drill Stem Tests,  
Well Stimulation and  
Production Tests

Formation            Top            Bottom

Fort Scott	4431	4457
Mississippian	4530	4535
Mississippian	4536	4543

7" - 30" - 30"  
Recovered 10' mud w/few spots of oil.  
IFP 44#, FFP 44#, FBHP 55#.

10" - 30" - 30" - 30"  
Recovered 10' oil cut mud w/1' free oil.  
IFP 20#, IHHP 1094#, FFP 20#, FBHP 890#.

10" - 45" - 90" - 45"  
Recovered 130' gassy oil (37° gravity),  
120' slightly oil cut muddy water, and 420'  
salt water. IFP 33-55#, IHHP 1285#,  
FFP 87-317#, FBHP 1051#.

SAMPLE TOPS

Anhydrite	1956 (+ 619)
B/Anhydrite	1987 (+ 588)
Topeka	3621 (-1046)
Heebner	3884 (-1309)
Toronto	3902 (-1327)
Lansing	3923 (-1348)
Fort Scott	4427 (-1852)
Cher. Shale	4454 (-1879)
B/K.C.	4260 (-1685)
Miss. Lime	4526 (-1951)
Miss. Dolomite	4531 (-1956)



DST (1) 4431-4457  
DST (2) 4530-4535  
DST (3) 4536-4543

0	70	Clay & Sand
70	301	Shale
301	745	Shale & Shells
745	950	Sand
950	1335	Shale
1335	1475	Shale w/sand streaks
1475	1700	Sand
1700	1775	Shale w/sand
1775	1956	Shale
1956	1987	Anhydrite
1987	2575	Shale
2575	3993	Lime & Shale
3993	4325	Lime
4325	4359	Lime & Chert
4359	4535	Lime
4535	4543	Lime & Chert
	4543	Rotary Total Depth

STATE GEOLOGICAL SURVEY OF KANSAS