

10% ME. 15 C.C. MEL. 1022

State **Kansas** County **Kiowa**
Company **Barbara Oil Company** Well No. **1**
Farm **Rice**
Survey **3538**

Block No. Sec. **18** Twp. **30 S** Range **16 W**
Co-Ord. Elev. **1882 D/F**
1884 K/B

NE SW SW

Contract for:
Barbara Oil Company

To be comm. by **12-10-56**
5000' Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line **990** Ft. from S. Line

990 Ft. from W. Line Ft. from E. Line

Date	Depth	
12-13-56		MI & RUR
12-14		371' w/12$\frac{1}{4}$" hole
		603' w/7-7/8" hole
		8-5/8" @ 373' w/225 sx. cem.
12-17	2309'	Drlg.
12-18	2647'	Drlg.
12-19	3061'	Drlg.
12-20	3402'	Drlg.
12-21	3717'	Drlg.

Date	Depth'	716013
12-22	3866'	B.T.P. pipe hung @ 3816'
12-23		Spotted oil, couldn't free pipe
		backed off drill pipe from
		9 drill collars @ 3545'
12-24		Ran wash over pipe, hung
		wash over pipe @ 3465', pulled
		wash over pipe except 4½ jts.
12-25		Shut down from 8:00 until
		midnight. To run jars & 17 dr
		drill collars to fish out
		wash over pipe stuck @ 80'
		above drill collars
12-27		Still fishing
12-28	11:30 A.M.	- no report from field
12-29		Set cement plug @ 3455' - top
		of plug 3350' - set for 36 hrs
12-31		Drilled cement - circ. to buil
		up mud - to whipstock
1-2-57		WOC
1-3		No report
1-4	3228'	Drlg.
1-7	3427'	Drlg. (off 5¼°)
1-8	3635'	Drlg. (4¼° off @ 3467'. Trip
		3538' 226'-27¼ hrs. 47 visc.
		10# wt. 12 c.c. wtr. loss

10 C.I.C. 2 LNU 102 27

776013

Date	Depth	Description
1-10	3887'	Sj tops:
1-12	3887'	Heebner (-2003)
	4054'	Brown Lime (-2170)
1-17	4073'	Lansing (-2189)
1-11-21	4635'	Cong. (-2751)
1-10-21	4668'	Kinderhook (-2784)
	4725'	Viola (-2841)
1-2-21	3180'	DST #1 - 4625-80' - Op 1 hr.,
		SI 20', Rec. 60' drlg. mud,
		FP 105-110# BHP 325#
		To plug
1-18-57	4734'	R.T.D. Bridging plug & 1/2 sk.
		hulls and 1/2 sk. cem. @ 360'
		Bridging plug & 1/2 sk. hulls
		and 10 sx. cem. @ 40'
		Plugging completed 1-17-57
		CONCRETE LOG: