


State Kansas County Sumner
 Company Shawver-Armour, Inc. Well No. 1
 Farm 30 (-Seydell "A")
 Survey 3 (-3220)
 Block No. 8 Sec. 30 S Range 1 E
 Co-Ord. 1273-K/B Elev. 1273-K/B



\$2,500.00
Dry Hole Contribution
 50% - A. A. Seeligson, Jr.
 25% - Chicago Group
 25% - M-R Oil Co.

3800' Sp. test to be comm.
 on or before 12-15-58

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330 Ft. from S. Line
 Ft. from W. Line 330 Ft. from E. Line

Date	Depth	
11-15-58	3110	Spud - set 8-5/8" @ 268'
11-15-58	3012	w/225 sx. cem., 2% c.c.
	3101	P.D. @ 6:30 A.M.
11-17	865	Drlg.
11-18	1710	Drlg.
11-19	2160	Drlg.
11-20	2310	Drlg.
11-21	2619	Drlg. (2 twists-off in 24 hrs)
	2479	Stalnaker (-1206)

Date	Depth	
11-24	3153	Drlg.
11-30	2808	City Kansas/(-1535)
11-12	3045	Base Kansas City (-1772)
11-25	3375	Drlg.
11-26	3477	Drlg.
	3401	Miss. (-2128)
11-28	3675	Drlg.
11-29	3770	Drlg.
DST #1 - 3856-3864 $\frac{1}{2}$ - Op 90", fair blow,		
		Rec. 60' gas, 60' GCM & 240' GCSW
		BHP (20") 1435-1295#, FP 0-145#
	3933	R.T.D.
		D & A - 11-30-58
(Log)		Tops: (Sample)
		Stalnaker 2471 (-1198)
		Base Stalnaker 2601 (-1328)
2809	(-1536)	Kansas City 2808 (-1535)
3036	(-1763)	Base Kansas City 3044 (-1771)
3402	(-2129)	Mississippian 3401 (-2128)
3805	(-2532)	Kinderhook 3804 (-2531)
3863	(-2590)	Simpson 3862 (-2589)
3930	(-2657)	Arbuckle 3931 (-2658)