

State Kansas County Barber


Company Seidman Oil & G. Co. Well No. 11

Farm W. A. Newbirk

Survey \_\_\_\_\_

Block No. \_\_\_\_\_ Sec. 9 Twp. 33<sup>rd</sup> Range 11<sup>W</sup>

Co-Ord. \_\_\_\_\_ Elev. \_\_\_\_\_



See new new Rig #1

NOTE: Show Sketch of Lease and Well Location in Above Space

990 Ft. from N. Line \_\_\_\_\_ Ft. from S. Line \_\_\_\_\_

990 Ft. from W. Line \_\_\_\_\_ Ft. from E. Line \_\_\_\_\_

Date	Depth	
		<u>Apr 3-17-55</u>
<u>3-17-55</u>		<u>M.I.R.T</u>
<u>3-18</u>		<u>Cementing surface casg.</u>
<u>3-19</u>		<u>10 3/4" @ 240' w/200 lb cems</u>
		<u>4 cc 2% gll.</u>
<u>3-21</u>	<u>2159</u>	<u>Dreg plug</u>
		<u>Dreg (1° off @ 2049)</u>
<u>3-22</u>	<u>2655</u>	<u>Dreg (ok @ 2555')</u>
<u>3-23</u>	<u>3052</u>	<u>Dreg (ok @ 2925)</u>
	<u>3540</u>	<u>Reelined</u>
<u>3-24</u>	<u>(3422</u>	<u>mudding up (ok @ 3210)</u>
	<u>3641</u>	<u>Douglas</u>
<u>3-25</u>	<u>3684</u>	<u>Circ for samples (Douglas)</u>
		<u>1/4" oob @ 3530</u>

716092

Date	Depth	
3-26		Cored 3684-3704' - 100% Rec.
		DST 3678-84 op 1 hr. 49 mins 1" choke
		on top - I.F.P-772 <sup>#</sup> F.F.P-1156 <sup>#</sup>
		BHP-1490 <sup>#</sup> . Gas in 3"
		6,160,000 in 5"
		4,735,000 in 15"
		5,210,000 in 30"
	3720	Dreg
	3742	Landing, K.C.
3-27	3876	Dreg
3-28	4010	Dreg
3-29	4136	Dreg (1° off 4057)
3-30	4231	Dreg (3/4° off 4216)
3-31	4370	Dreg (1 1/4° off 4319)
	4390	miss
4-1	4429	Coring
4-2	4450	Taking DST #2
		Cored 4399 to 4450 (100% rec)
4-4	4525	R.T.D. Log TD 4523
		Running 5 1/2" 2' off bottom
		5 1/2" @ 4523 w/ 300 sp cm,
		2% Stratacrete. PD 12:15 pm 4-4
4-6	m.o.c.s	
4-7		Running Helix Log