


State Kansas County Barber
 Company Magnolia Petro Corp. Well No. 2
 Farm Robert B. Cook
 Survey

Block No. Sec. 20 Twp. 34 Range 12

Co-Ord. S.P. 4750 Elev. 1537



Rig #1

100% Magnolia Petro. Corp.

*call Bob Young
 Home AM 5-6938*

NOTE: Show Sketch of Lease and Well Location in Above Space

990 Ft. from N. Line

Ft. from S. Line

1650 Ft. from W. Line

Ft. from E. Line

Date	Depth	
		<i>Spd 12-4-55</i>
<i>12-3</i>		<i>M.R.S.</i>
<i>12-5</i>	<i>355</i>	<i>Running surface</i>
<i>12-6</i>		<i>9 5/8" @ 355 w/300 AP. P.D. 9:15 am 12-5</i>
		<i>to S. U. S. this morning.</i>
<i>12-7</i>	<i>1693</i>	<i>Drilg</i>
<i>12-8</i>	<i>2193</i>	<i>Drilg (3/4" @ 2124)</i>
<i>12-9</i>	<i>2644</i>	<i>Drilg</i>
<i>12-10</i>	<i>3049</i>	<i>" (1/4" @ 2827)</i>
<i>12-12</i>	<i>3908</i>	<i>Drilg</i>

Date	Depth	716109
12-13	4187	Dreg
12-14	4399	Dreg (1° off) 4264)
12-15	4549	Dreg (1/2° @ 4437
12-16	4688	Dreg (1° @ 4581)
	4756	Missed (-3219)
12-17	4780	Taking det 4755-80
12-19	4850	R.T.D. Laying down drill pipe - ready to run cog.
12-20	4853	R.T.D. corrected 5 1/2" @ 4852 w/ 150 at cem. P.D. 7:50 pm 12-19
12-21	MIST	
12-22		Bailing hole down)
12-23		Perf. Ready to run thg.
12-27		3 runs on 12-23. Lost hole downs. Do not have as much gas as before. Press.
12-28		Have 200' wire in thg. Making very little gas.
12-29		Have 1200' press on thg. 2L 60 BPH (mostly lost air)
12-30		Thg press - 140"; op th 4". Have rec. 124 bbls fluid. Making 1+ mile of g.
12-31		Graced again & just finished swabbing
1-1-56		Making 1/2 BPH. Rec. 208 bbls fluids.
1-2		Testing perfor 4780-96. Gas measured 519.000 cf. Spray of oil & wh

State Kansas County Barber


Company Magnolia Petr Co Well No. 2

Farm Robert B. Cook

Survey

Block No. Sec. 20 Twp. 34^S Range 12W

Co-Ord. Elev.



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
1-3	Drilled pipe 4780-90. Making 6 BFPH, 24% wt. Had no 191 lbs load. Tbg press-200 ⁺ ; 150 ⁺ press on separator, 1 ⁺ on op fl.	
1-4	Pulling tbg. To bring packer out of hole. It would not work.	
1-5	Compl @ 3/4 mile c/g. Cg press- 425 ⁺ , tbg-100 ⁺ , Separator-100 ⁺ 1 ⁺ op fl.	

[illegible]