

State Kansas County Barber

Company Wm. Graham Oil Co. Well No. 1

Farm Emma F. Magnison

Survey _____

Block No. _____ Sec. 2 Twp. 33S Range 13W

Co-Ord. _____ Elev. 1648 KB

C SW NW

Rig #3

100% Wm. Graham Oil Co.

Cities Service Farmout
AM 5-5621

Geol: Jim Condon:

Medicine Lodge Pool 3950' test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 660 Ft. from S. Line _____

660 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
		SPD 7-28-54
7-29		8 5/8" @ 423' w/250 sx cem &
	4 c.c.	P. D. 8 a.m. 7-29-54
7-30	721	Drlg
7-31	1835	Drlg
8-2	2575	Drlg
8-3	3085	Drlg
8-4	3432	Drlg
8-5	3680	Drlg
		DST 3580-97' Op 60", Cl 20", Rec 230'

Date	Depth	716115 3301
	mdy wtr.	IF 100#, FF 180# BHP 1450#
	Hydro Static	2240#
8-6	3807	Doug.
	DST 3787-3817'	Op 1 1/2'. Rec 92' mud.
		Gas to surf in 11"
		350,000 in 1 hr
		434,000 in 1 1/2 hr
		IF & FF 140# BHP 800#
	DST 3815-27'	Op 60". Gas to surf in
		3". Ga. 3,310,000 cfg. IF 330,
		FF 620. BHP 940 - 30". Rec 90'
		Sli WC mud
	3817	Drlg. To drill 10' and test
8-9	3833	R.T.D. 5 1/2" @ 3815' w/50 sx
		Ran Sj
8-25		MICT
		C.O. to 3833
		2,600,000 cfg