

State Kansas County Barber


Company Lion Oil Co. Well No. 1

Farm Anna

Survey

Block No. Sec. 23 Twp. 33 Range 14

Co-Ord. Elev. 1900 KB



100% - Lion Oil Co.

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 1650 Ft. from S. Line


Ft. from W. Line 990 Ft. from E. Line

Date	Depth	
		<u>Spd 10-2-55</u>
<u>10-1-55</u>		<u>MORJ.</u>
<u>10-3</u>		<u>8⁵/₈ @ 273' w/175' of porous.</u>
		<u>P.D. @ 6:00 A.M. 10/3</u>
<u>10-4</u>	<u>280</u>	<u>Drilg. Drilled plug + 7' chis.</u>
		<u>morning work is slow because</u>
		<u>of mud.)</u>
<u>10-5</u>	<u>2008</u>	<u>Drilg. (1/2" @ 1812)</u>
<u>10-6</u>	<u>2649</u>	<u>Drilg. (1/4" @ 2334)</u>
<u>10-7</u>	<u>3206</u>	<u>Drilg. (1/4" @ 2772)</u>

Date	Depth	716117 (3/4° @ 3411)
10-8	3695	Back on bottom your trip
10-9	4079	Dreg
10-10		Det 4115-63, op, lv, cl 20". Str bl throughout. Rec 310' mdy SW. App-80, 334-200, Bhp 1310".
	4283	Dreg.
10-11	4446	On bottom after bit trip (1° @ 4445)
10-12	4635	Dreg. (Hebner 12' lower Lunken "a" 1 & 2' higher Lions Bait "B" 1)
10-13	4750	Taking Det in Massey 4729-50
10-14	4816	Miss (- 2916) Getting ready to take Det #3 4816-25
10-15	Det #3 4816-25	op 63", cl 30" Rec 35' qcm 98,000 cfm in 10" 142,000 ✓ " 30" 138,000 ✓ " 55" IF+FFP-30" IBHP-1800" FBHP-1615"
10-16	Det #4 4825-40	op, lv, cl 20" Sd bl

State Kansas County Barber
 Company Leon Oil Co Well No. 1
 Farm Anna
 Survey _____
 Block No. _____ Sec. 23 Twp. 33^S Range 14^W
 Co-Ord. _____ Elev. 1900 KB

Sur N.E. Sec



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Res 10' gcm. I Bhp - 175 ⁺
		3 Bhp 285. IF-30 ⁺ , FF-15 ⁺ .
	4867	Drlg
10-17	Det #5	4840-90, op. 1 hr, cl 20". Bd
		bl. Rec 30' sli gcm. Bhp-320 ⁺
	Det #6	4890-4907, op 1 hr, cl 20". Bd
		bl but no gas. Rec 40' gcm.
		Bhp - 1030 ⁺
	4965	RTD (Lj 4966) Running 5 1/2"

Date	Depth	716117
10-18		5 1/2" @ 4965 w/225 approx P.D. 12:30 pm 10-17-55.
10-19		MICT
10-20		Cleaning out. Is perf about noon
10-21		Perf 4886-91' w/15 ^s (a little gas) acidized w/1000 gals. Set plug @ 4873'. Perf 4852-63. Acidized w/1000 gals. Lock app 35 lbs having load back. Making 1 Bu ph, no gas Do set plug and perforate up the hole and zone. 10-22 Set plug @ 4834. Perf 4817-26 w/54 ^s Traced w/5000 ⁺ sd = 5000 gals oil. Made app 5 mil cff. 10-24 Gas decreased to ^{1,200,000} 254,000 cf. Traced w/5000 gals sd-oil and 15000 ⁺ sand. To start testing @ 8 am 10-25 Making 2 BFPH (Load oil) and 3 mil. cff. Testing. 10-26 Testing. Making 2,820,000 cff. no gas compl 10-26-55.