

State

Kansas

County

Barber

Company

Magnolia Petroleum Co.

Well No.

1

Farm

Olson "C"

Survey

Block No.

Sec.

21

Twp.

34^s

Range

12^w


Co-Ord.

Elev.

1459 KB

See page 10

Key #1



100% - Magnolia Petroleum Co.

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

1650

Ft. from S. Line

1650

Ft. from W. Line


Ft. from E. Line

Date	Depth	
		Spd 1-21-56
1-20-56		M & K J
1-21	300'	Drilg.
1-23		9 5/8" @ 353' w/300 rd cm.
		P.D. from 1-21-56
	1390	Drilg.
1-24	2000	Drilg.
1-25	2489	Drilg. (3/4" @ 2353)
1-26	2965	Drilg. (1/2" @ 2591)
1-27	3407	Drilg. (3/4" @ 3347)

Date	Depth	716151
1-28	3908	Delg. (1° @ 3551)
1-29	4159	Delg.
1-30	4387	Delg. ($1/4^{\circ}$ @ 4300)
1-31	4490	Delg. ($3/4^{\circ}$ @ 4407)
2-1	4599	Making trip
2-2	4697	Miss (-3236)
	4725	Taking D&S 4700-25 sp. 1 hr., d 20", 3 bl. faint odor, Rec. 30' sli GCM - 1F & F.P. - 15# B.H.P. - 530#
2-3	4760	Taking D&S 4725-60 sp 92", d. 30", Gd. Steady bl., Rec. 50' dely. med. No Gas - 1F & FF - 15# BHP - 785# R.D. - Raising down D.P.
2-4	4793	5 1/2" @ 4792' w/150 sp.
2-6		passing P.D. @ 4:45 P.M. 3/4 Last circulation while pumping plug down. Plug @ 3250' M.I.C.T.
2-6		
2-7		Bailing hole @ 3000'
2-8		Lost pig gun in hole. Fishing.

State Kansas County Barber
 Company Magnolia Petr Co Well No. 1
 Farm Alton "C"
 Survey -
 Block No. - Sec. 21 Twp. 34^S Range 12^W
 Co-Ord. - Elev. 1459 KB

SW NE SW



100% - mag.

Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
2-9	Drilling hole down. Can get down to 1000'.	
	W.O. orders - May cement	
2-10	Squeezed last night.	
	W.O.C.	
2-11	Bailing hole. Shld be dry cement now	
2-13	Making 1 BPH with a little gas.	
2-14	Acidized. Used Tot. load 109 lbs.	
	Have rec 105. Spray of water	

Date	Depth
	716151
	the last Lv.
2-15	Making 1,630 Mfg ($\frac{3}{4}$ choke, separator press - 50 [#] , thg press - 160 [#] ; reg press - 460 5 [#] on up fl
2-16	Completed 2-15-S6.