

State Kansas County Ellis

Company Okmar Oil Co. Well No. 3


Farm Session "B"

Survey _____

Block No. _____ Sec. 15 Twp. 11^s Range 19^w

Co-Ord. _____ Elev. (1985 17F)

Rig # 3 1988 4/B



NOTE: Show Sketch of Lease and Well Location in Above Space

2310 Ft. from N. Line

Ft. from S. Line

Ft. from W. Line 1980

Ft. from E. Line

Date	Depth	
		<u>Spd 9-13-55</u>
<u>9-14</u>		<u>8 5/8" @ 205 w/150 sp can, 2%^o s.</u> <u>. P.D. 1 a.m. 9-14-55</u>
<u>9-15</u>	<u>244</u>	<u>S.U.S. 1 a.m. at 2 am table</u> <u>w/pty table. Has taken</u> <u>in for repair</u>
<u>9-16</u>	<u>1025</u>	<u>Dreg</u>
<u>9-17</u>	<u>1870</u>	<u>Dreg. (1° off @ 1560)</u>
	<u>1288</u>	<u>Anhydrite (+700)</u>
<u>9-19</u>	<u>2725</u>	<u>Dreg. mudded up @ 2600'. 4° @ 2614'</u>

Date	Depth	
		716198
	2958	Supaka (-1050)
9-20	Set #1	2963-75' op 1 hr. cl 20". Rec 50' sli ocm. BHP-800 ⁺
	3005	Dry
9-21	3160	Hebrew (-1272)
	3202	Laning (-1314)
	3210	Dry (1° off 3115)
9-22	Set #2	3238-45' op. 20" cl 15". Rec 15' sty mud. Press-0 On bottom w/ Set #3 3280-86
9-23	Set #3	3280-86, op 30", cl 15". Rec 255' wtr. IFP-0 FFP-150, Bhp- 1000 ⁺
	3442	Conglomerate
	3452	Dry
9-24	3528	amplitude (-1540)
	3537	R.T.D. Ready to run cog
9-25		5 1/2" @ 3530 w/ 200 ex cov. P.D. 5:30 pm 9-24-55