



SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Pyramid Corporation LEASE Anders No. 1 SEC. 15 TWP. 32S RGE. 4E

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SURFACE HOLE.	0	218		
SHALE SAND W/ LIME STREAKS	218	1838		
LIME W/ SHALE - IATAN,	1838	1870		
SAND W/ SHALE - STALNAKER.	1870	1975		
SHALE	1975	2284		
SHALE & LIME - IOLA	2284	2293		
SAND & SHALE - LAYTON	2293	2457		
KC LIME, BREAK @ 2560	2457	2560		
SHALE & LIME	2560	2590		
LIME & SHALE - CLEVELAND	2590	2661		
LIME - ALMONT	2661	2690		
			IATAN	1838
			STALNAKER	1870
			IOLA	2284
			LAYTON	2293
			K. C.	2457
			BASE KC	2560
			CLEVELAND	2590
			ALTAMONT	2661

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		8-5/8"	14#	220'	A cement	180	5 sxs Calcium-Chloride M/
PRODUCTION		5-1/2"	14#	2690'	50/50 PAS	200	18% Salt 6# Gelsonite

LINER RECORD

PERFORATION RECORD

Top, ft. X	Bottom, ft. X	Sacks cement Z	Shots per ft. 2 shots	Size & type 3-1/2" DMI 'S	Depth interval 2600'-2615'
---------------	------------------	-------------------	--------------------------	------------------------------	-------------------------------

TUBING RECORD

Size 2-1/2"	Setting depth 2624'	Packer set at X			
----------------	------------------------	--------------------	--	--	--