

7-28-17E

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 UNION NATIONAL BANK BUILDING - WICHITA, KANSAS

COMPANY **Scott & Wangler**

SEC. 7 T. 28 R. 17 E

FARM **O.R. Larson**

NO. **2.**

LOC. **SE NW SW NE**

500' WL 700' SL NE 1/4

TOTAL DEPTH **848'**

COMM. **3-22-27**


COMP. **3-27-27**

COUNTY **Wilson**

SHOT OR TREATED

CONTRACTOR

ISSUED



CASING

20

10

15

8

12

6

13

5

11'
515' P

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATION

soil	4
clay	8
shale	78
lime	96
shale	135
lime	200
shale	210
sand	330
lime	410
shale	448
lime	467
shale	477
lime	513
shale	597
lime shells	635
shale	645
lime	660
shale	734
lime	737
shale	740
lime	762
shale	765
lime	769
shale	796
lime	814
gas shale	819 gas
lime	824
gas shale	829 gas
shale wh	834
sand	848
Total Depth.	

Tubing: 1" at 814
2" at 848

Packer 810
Cage 815
Hemmeroth 814