


State Kansas County Ellis  
 Company Continental Oil Co. Well No. 1  
 Farm Alayna Bass  
 Survey (Boos)  
 Block No. \_\_\_\_\_ Sec. 20 Twp. 15 Range 17<sup>w</sup>  
 Co-Ord. \_\_\_\_\_ Elev. 1957 KB



*100% - Continental Oil Co.*

*Key #3*

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 990 Ft. from S. Line \_\_\_\_\_

1650 Ft. from W. Line \_\_\_\_\_ Ft. from E. Line \_\_\_\_\_

| Date        | Depth       |                                                                        |
|-------------|-------------|------------------------------------------------------------------------|
|             |             | <i>Spd 5 pm 2-8-56</i>                                                 |
| <i>2-7</i>  |             | <i>Moving in.</i>                                                      |
| <i>2-8</i>  |             | <i>Delayed because of snow.<br/>to get started up today.</i>           |
| <i>2-9</i>  |             | <i>Cementing surface log.</i>                                          |
| <i>2-10</i> |             | <i>13 3/8" @ 200' w/1500 lb cem,<br/>3% gel. 2 cc. P.D. 8 a.m. 2-9</i> |
|             | <i>858</i>  | <i>Drilg. SUB 9:30 pm 2-9</i>                                          |
| <i>2-11</i> | <i>1105</i> | <i>Anhydrite</i>                                                       |
|             |             | <i>8 5/8" @ 1117 w/600 lb. P.D. 3:45 a.m. 2-11</i>                     |

2-12-58

716457

| Date           | Depth             |                                                                                                                                                                         |
|----------------|-------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 2-12           | 1200              | Dreg                                                                                                                                                                    |
| 2-13           | 2210              | Dreg ( $1\frac{1}{2}^{\circ}$ @ 1930)                                                                                                                                   |
| 2-14           | 2595              | Dreg ( $1^{\circ}$ @ 2450)                                                                                                                                              |
| 2-15           | 3020              | Dreg (Have missed up)                                                                                                                                                   |
| 2-16           | 3217              | Going in hole w/new bit.                                                                                                                                                |
| 2-17           | 3210              | Heelnew (-1253)                                                                                                                                                         |
|                | 3262              | Running (-1305)                                                                                                                                                         |
|                |                   | Det #1 3265-3300, op 1 hr, at 20". Nk<br>bl for 27". Rec 60' mud.<br>IF-60, FF-90. BHP-850 <sup>+</sup>                                                                 |
|                | 3332              | Dreg ( $3\frac{1}{4}^{\circ}$ @ 3300)                                                                                                                                   |
| 2-18           |                   | Det #2 3307-88, op 1 hr, at 20". Gas to<br>surface in 55". Nk bl through<br>cut. Rec 55' hr 0x9cm,<br>120' 0x9cm, 120' mdy oil.<br>IF-70, FF-120. BHP-1010 <sup>+</sup> |
| Det #3 3532-37 | 3530 <sup>+</sup> | arb Rec 540' clean oil, 180' mdy oil 9 3/8 gas                                                                                                                          |
| 2-19           | 3537              | R.T.D. <sup>2-19-980</sup> Running 5 1/2"<br>5 1/2" @ 3531 w/100 sh. com,<br>3 1/2 gel. P.D. 1 p.m. 2-20.                                                               |