

Schermerhorn oil co.
 # K-33 Multine
 K

Completed in 1959

177
 44
 45
 10' - 7" Surface Pipe
 2" H-40 pipe cemented at 1016.5' and perforated into Bartlesville sand

Schermerhorn Oil Corporation
 Multine K-33
 Section 8-28-17 Wilson County, Kansas
 Rotary Commenced: July 29, 1959
 Drilling Completed: July 30, 1959
 Contractor: Keas Drilling Company, Inc.

Thickness Strata	FORMATION	Total Depth
2	Soil	2
3	Clay	5'
25	Lime Shells	30
215	Shale	245
5	Lime	250
5	Shale	255
5	Lime	260
12	Shale	272
42	Lime	314
5	Shale	319
16	Lime	335
31	Shale	366
10	Lime	376
5	Shale	381
31	Lime	412
5	Shale	417
21	Lime	438
31	Shale	469
5	Lime	474
10	Shale	484
5	Lime	489
5	Shale	553
64	Shale	563
10	Lime	661
98	Shale	666
5	Lime	671
5	Shale	688
17	Lime	725
37	Shale	745
20	Lime	750
5	Shale	755
5	Lime	753
198	Shale	953
22	Sandy Shale	975
44	Core	1019 T.D.

21' - Surface Pipe
 2" H-40 pipe cemented at 1017.5' and perforated into Bartlesville sand