

State

Kansas

County

M. Plesson

Company

Continental Oil Co. Well No. 12

Farm

J. P. Hillman

Survey

Block No.

Sec. 29


Twp. 21<sup>s</sup>Range 1<sup>w</sup>

Co-Ord.

See new

Elev. 1485 KB

Reg #3



100% - Continental Oil Co.

NOTE: Show Sketch of Lease and Well Location in Above Space

990

Ft. from N. Line

Ft. from S. Line

1650

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Spd 6-2-55
6-1		MORJ
6-2		"
6-3		8 <sup>5</sup> / <sub>8</sub> " @ 253 w/200 sp cem, 3 C.C. P.D. 3:30 am 6-3-55.
6-4	376	Dreg
6-5	990	Dreg
6-6	1899	Dreg
6-7	2295 2495	Lossing (-810) Dreg (1/2" off 2218)
6-8	2793	Dreg (mudded up)

Date	Depth	716496
6-9	3000'	Displacing mud w/oil cand.
6-10	3059	Changing back to chemical mud
6-11	3134	Coming out of hole for bit trip
6-13	3283	Cored 21'. Had regained lost circ. Going back in hole to ream out.
6-14	3286	Coring & having lost circ. Tble.
6-15	3305	Coring (16" per ft) 20 core to 3317)
		(Lost circ for 2 hrs last night)
6-16	3390	Going back in hole with core barrel.
6-17	3429	Cored from 3390-3429 Circulating getting ready to DST
	DST 3403-13	op 45", cl 15". Rec 1850' free oil. 1FP-260, FFP- 730"; BHP 1140.
6-18		Tried to log. Had to core hole. Trying again @ 7:30am
6-20	3439	R.T.O. Set 5 1/2" @ 3437 w/225 sp cem. P.D. 9:25 pm 6-18-55.

Gravity of Simpson oil 27.6°