

State Kansas County Roops

Company Okman Oil Co. Well No. 5


Farm Road

Survey

Block No. Sec. 9 Twp. 10^N Range 20^W

Co-Ord. C. P. 3350. S. P. 3550. Elev. 2221 KB

ne sw sw Rig #1



100% Okman Oil Co.
817 Wm. Hall St Sdgy
AM 7-8211

call Oil Trading Corp.
HO 4-7096
Geol: Joseph Reichman
Tulsa, R.I 2-8612

NOTE: Show Sketch of Lease and Well Location in Above Space
and at call point
+ call Mr Limonard AM 5-9852
Name AM 77039

Ft. from N. Line 990 Ft. from S. Line

990 Ft. from W. Line Ft. from E. Line

Date	Depth	
		<u>Spd 9-4-55</u>
<u>9-6</u>		<u>8 5/8" @ 204' w/1500 ft cem. 2°C</u>
		<u>P.D. 2:15 am 9-5. To L.A. 8.9am</u>
<u>9-7</u>	<u>1695</u>	<u>Anhydrite (+ 526)</u>
	<u>1875</u>	<u>Dreg (1 1/2° off 1806)</u>
<u>9-8</u>	<u>2625</u>	<u>Dreg (Straight hole @ 2422)</u>
<u>9-9</u>	<u>3085</u>	<u>Dreg (1/2° @ 2727)</u>
<u>9-10</u>	<u>3395</u>	<u>Dreg (1/4° @ 3395)</u>
<u>9-12</u>	<u>3450</u>	<u>Heubner (-1229)</u>
	<u>3475</u>	<u>Coranto (-1254)</u>

12-13-55

Date	Depth	716554
	3493	Lansing (-1272)
	Lat #1	3519-45. op 1 hr, cl 15'
		Rec 290' sh. OC mdy wtr.
		IF-50, 33-115. Bhp 1060 ⁺
	3700	On bank w/dat #2. IF-50 app. 140 BHP 1090
9-13	Lat #2 3660-3700	3660-3700. op 1 hr, cl 15". Rec 300' med to hr OC m.
	3780	On bottom w/dat #3
	3781	Arbuckle (-1560)
	Lat #3	3782-87, op 1 hr, cl 15". Rec 90'
		oil + 30' mdy wtr. Bhp-200 ⁺
9-14	3787	R.J.D. 5 1/2" @ 3784' w/150
		sk cems. P.D. 10:30pm
		9-13-55