


State Kansas County Rock
 Company Colorado O. & G. Corp Well No. 2
 Farm Ingber Schneider
 Survey

Block No. Sec. 32 Twp. 10^s Range 20^w

Co-Ord. Elev. 2158 KB
C. E/2 S e/4 Twp/4 King #1



100% - Colorado O. & G. Corp
 430 W Douglas
 AM 5-1661

NOTE: Show Sketch of Lease and Well Location in Above Space

1980 Ft. from N. Line Ft. from S. Line
2310 Ft. from W. Line Ft. from E. Line

Date	Depth	
		<u>Spd 6-8-55</u>
<u>6-8</u>		<u>R.U.R.</u>
<u>6-9</u>		<u>8 5/8" @ 232 w/ 1.25 sp/cm,</u> <u>3 gal, 3cc. P.D. 11:45 pm 6-8</u>
<u>6-10</u>	<u>1100</u>	<u>Drly</u>
<u>6-11</u>	<u>2304</u>	<u>Drly (3/4" off, 2304)</u>
<u>6-13</u>	<u>3287</u>	<u>Drly (Have mudded up)</u>
<u>6-14</u>	<u>3482</u>	<u>Drly.</u>
	<u>3431</u>	<u>Lancing 4/5. (-1273)</u>
<u>6-15</u>	<u>DST 3510-</u>	<u>20, op 1 hr. cl 20". Fair</u>

Date	Depth	716556
		bl throughout. Rec 150' fluid (90' lightly ocm + 60' SW with scum oil) IFF-0, FFP-15 th BHP-1170 th
		3595 Dreg.
6-16	DST #2 3558-3600, op 1 hr, cl 20"	Gd bl throughout. Rec 365' m + GCO, 140' gas in pipe. IF-0 FF-90 th , BHP-1125 th
	DST #3 3607-37, op 1 hr, cl 20"	Mk bl for 5". Rec 20' dreg mud. Pressure-0
	3632	Back on bottom w/new bit.
6-17	3734	Ar buckle (-1576)
	3740	Running DST #4.
6-18		Logging
6-20	3775	R.T.D. 5 1/2" @ 3680 w/100 sl Permit. P.D. 8:30 p.m. 6-18-55.