

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

18623
15-32-4E


CASING RECORD

LOCATION NE SE NW

SEC 15 T 32 R 4 E.

10" 1668 FARM State
20" 25 8 14 2614 COMPANY J. A. Hull.
15 1-2 345 6 5-8 3258 CONTRACTOR
12 1-2 1043 5 3-16 COMMENCED 2/5/27.

NO. 5 COUNTY Cowley



TOTAL DEPTH SHOT QUARTS BETWEEN
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO J. A. Hull,

COMPLETED 4/4/27.

Tulsa, Oklahoma.

ELEVATION 1245

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 1000 bbls.

REMARKS 5/14/27.

Formation	Depth	Formation	Depth	Formation	Depth
cellar	8	blue shale	1220	white lime	3160
red rock	23	broken lime	1230	greenish lime	3176
gravel	28	blue shale	1260	green shale	3192
white shale	35	(1 B. W. at 1235')		grey lime	3205
red rock	38	lime	1275	black shale	3266½
lime	40	blue shale	1285	brown lime	3268
blue shale	58	lime	1290	brown lime pay	3277
lime	65	blue shale	1320		
red rock	72	lime	1345	Total Depth	3277'
lime	76	blue shale	1365		
blue shale	100	broken lime	1368		
red rock	110	sand water 10 B. hr.	1380		
lime (2 B. W. hr.)	150	sandy shale	1400		
red rock	165	lime	1406		
sandy lime	195	white sandy shale	1412		
lime	205	sand water 10 B. hr.	1425		
blue shale	222	lime	1430		
broken lime	235	sand	1435		
blue shale	305	lime	1450		
red rock	315	blue shale	1467		
lime	317	lime	1520		
red rock	340	shale	1525		
lime broken	360	lime	1530		
lime	370	shale	1535		
grey shale	385	red rock	1568		
lime	400	lime	1570		
broken lime	410	blue shale	1585		
lime	418	lime	1600		
grey shale	430	blue shale	1646		
lime	510	sandy shale	1655		
white shale	530	blue sandy shale	1804		
(10 B. W.)		(2 B. W. 1700')			
broken sand	540	lime	1808		
lime	550	blue shale,	1820		
blue shale	620	sandy shale	1850		
lime	630	lime	1852		
blue shale	648	water sand HFV 1855	1895		
lime	657	blue shale	1905		
blue shale	673	water sand	1955		
lime	678	blue shale	2044		
blue shale	755	lime	2054		
white shale	800	shale	2060		
lime shell	803	lime (4 BW hr.)	2075		
grey shale	830	black shale	2275		
lime	880	sand	2295		
white shale	900	lime	2300		
lime	920	sand show oil 2325'	2355		
grey shale	928	blue slate	2410		
lime	930	lime show gas 2415'	2530		
red rock	936	sand water HFV gas	2552		
blue shale	970	lime	2565		
lime	980	shale	2570		
blue shale	1030	sandy shale	2590		
broken lime	1040	blue shale	2610		
lime	1050	lime	2740		
broken lime	1065	grey shale	2930		
lime	1078	chat	2955		
blue shale	1160	white lime	2987		
lime	1200	black lime	3125		