

15-16S-25W

D R I L L E R S L O G

#1 Smith

CASING RECORD:
8 jts. new 20#
8-5/8" surface
casing

COMPANY: Palomino Petroleum
CONTRACTOR: Strata Drilling Company

DESCRIPTION: NE SE NW
Section 15-16S-25W
Ness County, Kansas

TOTAL ROTARY
DEPTH: 4580'

COMMENCED: August 23, 1978

ELEVATION: 2574' KB

COMPLETED: August 29, 1978

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale	0	335	Ran 320' new 20# 8-5/8" surface
Shale, sand	335	1971	casing; set and cemented at 325'
Anhydrite	1971	2006	with 200 sacks common cement, 2% gel,
Shale	2006	2650	3% C.C.; cement circulated. Plug
Lime and shale	2650	4425	down 8:15 p.m., August 23, 1978.
Lime	4425	4530	
Lime and shale	4530	4580	Ran 2 DST.
			Ran 1 electric log
			Hole plugged with 50-50 pozmix, 6% gel as follows: 70 sacks @ 825', 20 sacks @ 240', hulls and 10 sacks @ 40'. Plugging completed at 10:15 p.m., August 29, 1978.

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the
best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President