

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL COMPANY

SEC. 31 T. 25 R. 5E

FARM Robison NO. 60

LOC. NE SE SW
990' N. 330' E. SW Corner

TOTAL DEPTH 2484

COMM. 9-4-50

COMP. 10-5-50


SHOT OR TREATED

CONTRACTOR B & R Drlg. Inc; Drill In; Chet Myers

ISSUED 1-27-51

COUNTY Butler

KANSAS



CASING

8 5/8" 77' cem. w/65 sx
5 1/2" 2468' cem. w/150 sx

1407 Ind
ELEVATION 1406 R.T.B.

PRODUCTION 50 bbls. oil &
no wtr/ 24 hrs.

FIGURES INDICATE BOTTOM OF FORMATIONS

Note: All measurements taken from R.T.B.

(R.T.B. is 3.5' above grd.)

soil	2'	Az. w/500 gals. used 45.bbls.
lime	30	load oil. Recovered load oil.
shale	50	Az. w/1000 gals. used 55 bbls.
shale & shells	60	load oil. tested & recovered
lime	80	load oil.
lime & shale	420	
shale & shells	730	
lime & shale	914	
sand & shale	1020	
lime & shale	1245	
lime	1330	
lime, shale & sand	1580	
lime & shale	1770	
lime	1870	
lime & shale	2065	
lime	2138	
lime & shale	2426	
lime, shale & sand	2469, RTD	
line	2484	
Total depth		

Tops:

Lansing	1669
Base Lansing	1871
Kansas City	2010
Base Kansas City	2173
Arbuckle	2467

Steel Line Measure:

1007- 1007
1382=1384
1634=1634
1946=1946
2405=2405
2466=2469

Remarks:

I. P. 50 bbls. oil, 0 wtr, 24 hrs.
P.O. (Arbuckle az. & re-az.) (mach.)
S.O. 1763-81
S.S.O. 2014-28; S.O. 2039-50; S.S.O.
2071-83; 2090-2168; S.O. 2467-69;
2469-72; F.S.O. 2472-76; G.S.O. 2476-
80; F.S.O. 2480-84; Best Pay 2469-84'
First Free Oil 2469-72'
Total Fill up: 750' oil, 0 wtr. 23 hrs.