

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


19-16-25W

Company- SUN OIL CO.
Farm- Horacek No. 1

SEC. 19 T. 16 R. 25W
NW NW SE

Total Depth. 4600'
Comm. 11-25-58 Comp. 12-13-58
Shot or Treated.
Contractor. Prime Drlg.
Issued. 1-31-59

County Ness
KANSAS



Elevation. 2594'

CASING:

8 5/8" 315' cem w/250 sx.

Production. Dry

Figures Indicate Bottom of Formations.

clay & shale	40
sand & shale	320
shale & lime	1387
lime & shale	1771
limey shale	1970
lime	2008
shale	2275
lime & shale	2370
lime	2610
lime & shale	3445
lime w/sh. strks	3606
Topeka lime	3908
Lansing lime	4500
Conglomerate	4530
Reworked Miss. lime	4554
Dolomite (salt water)	4600
Total Depth	

TOPS: SCOUT

Topeka	3606
Heebner	3867
Lansing	3908
Conglomerate	4500
Mississippi	4530

DST#1 4562', packer 4535', op 45 min.
rec. 15' mud, FP 10#-20#, BHP 945#.

DST #2 T.D. 4600', packer 4563', op 1½
hrs., rec. 390' muddy salt water.
FP 72-196#, BHP 844#.